






DRAWING NO.
SD075496

REV	DATE	DESCRIPTION	ECO	BY	C'H'K.
B	01/25/2013 00:00:00 AM	NOTES AND INSTALLATION TOOLINGS UPDATED AS PER ECO MARKUP	30020	AD	MA

CATALOG NO.	ACCOMMODATES ALUMINUM CABLE: CONCENTRIC, COMPRESSED, COMPACT COPPER CABLE: CONCENTRIC ONLY	DIMENSIONS						INSTALLATION TOOLING (# CRIMPS)						DIELESS (# CRIMPS)	WIRE STRIP LENGTH
		B	LL	L	O.D.	O.D.P.	P	DIE INFORMATION		MECHANICAL		HYDRAULIC			
								COLOR CODE	DIE INDEX	MD6	Y34A	Y35, Y39 Y750, PAT750	Y46 PAT46		
AYP8	#6 STR (.184 DIA) 7 STR	1.00 [25]	---	1.85 [47]	.60 [15]	.23 [6]	.68 [17]	TAN	296	W241 (2)	A25AR (1)	U25ART (1)	U25ART (1)	MECHANICAL: MY29-3 (1) OH25 (1) Y81KFT (1) PAT644 (1)	1-1/16"
AYP6	#6 STR (.184 DIA) 7 STR	1.00 [25]	2.03 [52]	1.85 [47]	.60 [15]	.23 [6]	.68 [17]	TAN	296	W241 (2)	A25AR (1)	U25ART (1)	U25ART (1)		1-1/8"
AYP4	#4 STR (.232 DIA) 7 STR	1.00 [25]	2.03 [52]	1.85 [47]	.60 [15]	.23 [6]	.68 [17]	TAN	296	W241 (2)	A25AR (1)	U25ART (1)	U25ART (1)		
AYP2	#2 STR (.292 DIA) 7 STR	1.00 [25]	2.03 [52]	1.85 [47]	.60 [15]	.23 [6]	.68 [17]	TAN	296	W241 (2)	A25AR (1)	U25ART (1)	U25ART (1)		
AYP1	#1 STR (.332 DIA) 19 STR	1.00 [25]	2.03 [52]	2.01 [51]	.60 [15]	.26 [7]	.84 [21]	TAN	296	W241 (2)	A25AR (1)	U25ART (1)	U25ART (1)		
AYP1/0	1/0 STR (.373 DIA) 19 STR	1.00 [25]	2.03 [52]	2.01 [51]	.60 [15]	.29 [7]	.84 [21]	TAN	296	W241 (2)	A25AR (1)	U25ART (1)	U25ART (1)		
AYP2/0	#2/0 STR (.419 DIA) 19 STR	1.11 [28]	2.23 [57]	2.21 [56]	.86 [22]	.33 [8]	.84 [21]	WHITE	298	W660 (4)	A28AR (2)	U28ART (2)	U28ART (2)	Y81KFT (2) Y644 (1) MY29-3 (2)	
AYP3/0	#3/0 STR (.470 DIA) 19 STR	1.11 [28]	2.23 [57]	2.59 [66]	.86 [22]	.37 [9]	1.22 [31]	WHITE	298	W660 (4)	A28AR (2)	U28ART (2)	U28ART (2)		



VIEW AFTER INSTALLATION



TYPICAL LETTERING VIEW
CONNECTOR MARKING

- NOTES:
- MATERIAL: CONNECTOR - ALUMINUM
INSULATION COVER - E.P.D.M (SEE SA76839)
 - FINISH: TIN PLATED (CONNECTOR ONLY).
 - BARREL IS PARTIALLY FILLED WITH PENETROX™ AND SEALED.
 - SCRATCH BRUSHING OF ALL CONDUCTORS BEFORE MAKING INSTALLATION IS RECOMMENDED
 - REMOVED PER ECO 7081.
 - CATALOG #PUADP-1 ADAPTOR IS REQUIRED TO USE "U" DIES IN Y46 SERIES TOOLS.
 - OVERLAP CRIMPS.
 - ONLY THE CONCENTRIC CABLE DIAMETERS ARE SHOWN.
 - CONDUCTOR INSERTION LENGTH MINIMUM.
 - PACKAGED IN CLEAR POLYBAG.

11. DIMENSIONS IN BRACKETS [] ARE IN MILLIMETERS ROUNDED OFF TO THE NEAREST MILLIMETER, UNLESS OTHERWISE NOTED, AND ARE FOR REFERENCE ONLY.

- FOR USE BY CUSTOMERS THAT HAVE THIS HYPRESS™. NO NEW Y34A HYPRESS™ TOOLS ARE BEING PROCESSED.
- NOT CSA APPROVED FOR USE WITH COPPER CONDUCTOR.
- UL LISTED FOR USE WITH COPPER OR ALUMINUM CONDUCTOR USIGN U-DIES OR Y81KFT SERIES OF DIELESS TOOLS.

- UL LISTED FOR USE WITH ALUMINUM CONDUCTOR ONLY USING Y644 DIELESS TOOLS.
- NOT UL LISTED OR CSA CERTIFIED WITH THIS TOOLING.
- USE Y644 OR PAT644 SERIES DIELESS HYPRESS™ ONLY WHEN INSTALLING 900 kcmil COMPACT ALUMINUM. MEETS UL TESTING REQUIREMENTS BUT IS NOT UL LISTED FOR USE WITH 900 COMPACT ALUMINUM.

TO ORDER BURNDY® PRODUCTS CALL
UNITED STATES
1-800-346-4175 (LONDONDERRY, NH)
CANADA:
1-800-361-6975 (QUEBEC)
1-800-387-6487 (ALL OTHER PROVINCES)
FOR PRODUCT INFO: <http://www.burndy.com>

WIRE CONNECTOR ACCESSORY COMPRESSION EQUIPMENT ADAPATOR	
ITEM NO:	N/A
CAT. NO:	AYP-- HYPLUG™ (TABLE)
DRAWN BY:	SDC 04/09/73
CHECKER:	JPS 04/16/73
DSN APPVL:	ELA 10/10/73
MFG APPVL:	--
QA APPVL:	D VARIO 11/26/96
MKT APPVL:	P WERTHMAN 10/18/96
PROD FAM:	--
PROJECT #:	--
DOCUMENT TYPE:	Sales
REL LEVEL:	Released

SCALE: 1:1
DRAWING NO: SD075496
REV: B
SHEET 1 OF 2

REV: PE0200